

**SCOPE OF WORK**

- Build Shed to Conceal and Secure Accessible Portable Toilet
- Set (4) 6"x 6" Pressure Treated Posts in 32" Deep Footers.
- Pour 6'-6" x 6'-6" Concrete Slab with (4) Eye Lag Bolts
- Build Three Sided Shed with T-111 Plywood Glued and Screwed to Framing Attached to Posts.
- Use 2"x 6" Rafters and Opaque F.G. Corrugated Panels for Low Pitched Roof.


**MATERIALS**

- (4) 10'-0" 6"x 6" Pressure Treated Posts
- (5) 8'-0" 2"x 6" Rafters
- (2) 4'-0" x 8'-0" Opaque Corrugated F.G. Panel
- (4) 8'-0" 2"x 4" Framing
- 14.08 Cubic Feet 3200psi Concrete.
- (4) 5/8" 18" Eye Lags Bolts
- Chain or Cable to Secure Unit to Concrete Slab.

**NOTES**

Verify Portable Toilet Size and Adjust Shed Size as Needed Prior to Construction.

**FIRST FLOOR PLAN**  
SCALE: 1/4" = 1'-0"



PROPERTY OWNER:  
**Pennsylvania  
Department of Conservation  
and Natural Resources**

PROPERTY TENANT:  
**Swatara Watershed  
Association, Inc.**

PROJECT LOCATION:  
**BORDNER CABIN**  
Old State Road  
Swatara State Park  
Bethel Township  
Lebanon County, Pa.

**M.H. WILLEMAN**  
P.O. BOX 345, MT. GRETTA, PA 17064  
(717) 864-3323

DATE: 5/12/09  
REVISION DATE:  
12/02/10  
6/18/12

SCALE: 1/4" = 1'-0"

File Name: Bordner Cabin

SHEET  
**A6**